



D. A. V. PUBLIC SCHOOL

RATWAR, Via - Mohania, Distt. - Kaimur (Bihar) PIN - 821 109.

Mob. : 9431089137 (M), 9123265865 (O), 9472880796 (O)

E-mail Id : dav_mohania11@rediffmail.com, davratwar@gmail.com • Website : www.davratwar.com

दयानन्द एंग्लो - वैदिक कॉलेज प्रबन्धकर्तृ समिति, नई दिल्ली द्वारा संचालित शिक्षा संस्था डी० ए० वी० = ज्ञान + विज्ञान

Co-educational, English Medium School Based On 10+2 Pattern & Syllabus of C.B.S.E; New Delhi.

PF Code No. - 966 • Pension Code No. - BR 8616 • Affiliation No. - 330160 • School No. - 65155

Ref. No. DAV/RAT/2025-26/88

Date 21/06/2025

TENDER NOTICE

FOLLOWING POINTS NEED ATTENTION

1. Sealed quotations as per above specification must be submitted to the School office DAV Public School, Ratwar, Mohania, Kaimur (Bihar) by 01.07.2025. The credentials/work experience of the contractor must be enclosed.
2. Brand/ Quality/ Quantity must be specified whenever acceptable.
3. Rates quoted should include all application taxes & all other expenses: no extra cost will be paid by the school in any case.
4. Lowest rates will be decided after final negotiation with the bidders by the constitution of committee for repair & maintenance, renovation & small construction of the school.
5. Uses of Electricity & Water by the contractor for said works include deduction of 1% of final approved bills.
6. All water proofing work should be executed with a minimum five - year warranty on the floor ensuring repairs in case of defects or damage.
7. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school will deduct TDS as per rule of income Tax.
8. The undersigned does not bind himself/ herself to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to all the article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/ she may decide.
9. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well contractor must full fill the terms and conditions of Government of India/ Bihar.

Head Office : D. A. V. College Managing Committee, Chitragupta Road, New Delhi - 55, Ph. : 011 - 23515951, Website : www.davcmc.net.in

Regional Office : Regional Directorate, D. A. V. Public Schools, Bihar Zone - F, C/o. D. A. V. Public School, Buxar (BR) - 802 136, Ph. : 06183 - 222280

E-mail : ardbiharzonet@gmail.com

[Signature]
PRINCIPAL
D.A.V. PUBLIC SCHOOL,
Ratwar, Mohania
Kaimur (Bihar) 821109



D. A. V. PUBLIC SCHOOL

RATWAR, Via - Mohania, Distt. - Kaimur (Bihar) PIN - 821 109.

Mob. : 9431089137 (M), 9123265865 (O), 9472880796 (O)

E-mail Id : dav_mohania11@rediffmail.com, davratwar@gmail.com • Website : www.davratwar.com

दयानन्द एंग्लो - वैदिक कॉलेज प्रबन्धकर्तृ समिति, नई दिल्ली द्वारा संचालित शिक्षा संस्था डी० ए० वी० = ज्ञान + विज्ञान

Co-educational, English Medium School Based On 10+2 Pattern & Syllabus of C.B.S.E; New Delhi.

PF Code No. - 966 • Pension Code No. - BR 8616 • Affiliation No. - 330160 • School No. - 65155

Ref. No. DAV/RAT/2025-26/88

Date 21/06/2025

10. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
11. The rates quoted by the contractor shall hold good up to finishing of the above said work No amendment will be accepted in the rate of renovation.
12. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect. Quotations which do not comply with the above conditions are liable to be rejected.

Members of Building Sub-Committee

Shri Ajay Goswami	:	Chairman
Mr. V. Anand Kumar	:	ARO
Dr. Birendra Kumar	:	Manager
Head DAV PS Aurangabad		
Head DAV PS Dhanupura Arah		
Mr. P.C. Das	:	Principal
Mr. B.K. Singh	:	Architect

Principal
D.A.V. PUBLIC SCHOOL
Ratwar, Mohania
Kaimur (Bihar) 821 109


Head Office : D. A. V. College Managing Committee, Chitragupta Road, New Delhi - 55, Ph. : 011 - 23515951, Website : www.davcmc.net.in

Regional Office : Regional Directorate, D. A. V. Public Schools, Bihar Zone - F, C/o. D. A. V. Public School, Buxar (BR) - 802 136, Ph. : 06183 - 222280

E-mail : ardbiharzonef@gmail.com


FOR TECHNICAL APPROVAL

ABSTRACT OF COST OF G.S. SHED FOR PARKING NEAR GARAGE SHED OF D.A.V. PUBLIC SCHOOL, RATWAR, MOHANIA, KAIMUR, BIHAR.						
Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		Area of shed = (20'-5"+15'-6"+15'-6")X17'-7" = 903.96 Sft				
		SECTION-I (EARTH WORK/SAND FILLING)				
1	2.8	Earth work in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kinds of soil	0.51	Cum	----	
2	2.28	Supplying and filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	0.10	Cum		----
		SECTION-II (R.C.C. /P.C.C. WORK)				
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level.				
	4.1.3	1:2:4 (1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size.)	0.51	Cum		
		SECTION-III (STEEL WORK)				
4	10.2	Structural steel work riveted or bolted in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	650	Kg		
		SECTION- IV (ROOFING WORK)				
5	12.1	Providing corrugated G.S. sheet roofing fixed with G.I.J. or hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 60 °) excluding the cost of purlins, rafters and tursses.				
	12.1.3	0.50 mm thick with zinc coating not less than 275 gm/sqm.	88.79	Sqm		----
		SECTION-V (FINISHING WORK)				
6	13.81	Applying priming coat:				
	13.81.4	With ready mixed zinc chromate yellow primer of				


PRINCIPAL
D.A.V. PUBLIC SCHOOL
Ratwar, Mohania
Kaimur/Bihar 82410

①

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		approved brand and manufacture on steel galvanised iron/steel works (second coat)	86.41	Sqm		
7	13.82	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade.				
	13.82.1	New steel work (Two or more coats)	86.41	Sqm		
		SECTION-VI (ACP WORK)				
8	MR	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets(each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF/Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc.				
		The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium items. The contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete, as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminium composite panel cladding (including width of groove) shall be measured in Sqm. Up to two decimal places.	7.10	Sqm		
		TOTAL				
		ROUNDING OFF				
		Cost of construction per S.Ft.				



PRINCIPAL
G.A.V. PUBLIC SCHOOL
Ratwar, Mohania
Kaimur (Bihar) 821109